

305 - AGGREGATE BASE AND AGGREGATE SHOULDERS

305.1 DESCRIPTION

This work shall be done in accordance with Sections 305 of the Standard Specifications except as otherwise modified herein. It shall consist of placement of aggregate base and aggregate shoulders at locations shown on the plans or determined by the Engineer.

305.2 MATERIALS

All aggregates for aggregate base construction shall comply with AB-3 Overland Park Modified contained herein or as on file with the City Engineer.

All aggregates for aggregate shoulder construction shall comply with Section 1113 of the Standard Specifications.

All aggregate material shall be obtained from a central mixing plant after being batched in a pug mill to the proper moisture content, as specified by the Engineer. If not specified elsewhere, the moisture content of AB-3, OP Modified material, as delivered to the project site, shall be MR-3-3.

305.3 MEASUREMENT AND PAYMENT

The Engineer will measure the aggregate of specified type by the square yard of placed material at the indicated depth.

Payment for "Aggregate Base" and "Aggregate Shoulder" at the contract unit prices bid is full compensation for the specified work.

No separate payment will be made for water or calcium chloride as it shall be considered subsidiary to other bid items.