

## **615 - STREET SWEEPING**

### **615.1 DESCRIPTION**

During the cold milling operation, the Contractor shall remove all cuttings and debris from the street by use of a self-propelled street sweeper with hopper. Recompact milling materials and all other materials not picked up the street sweeper shall be removed by other means by the Contractor. No material shall remain that would recompact or leave an unsuitable surface for subsequent overlay operations. Open faced brooms shall only be used when approved by the City Engineer.

At all other times the project site shall be kept clean, neat and orderly. The contractor shall keep all streets in a dust free condition. At any time the engineer may require additional sweeping to maintain the required dust free surface. Stockpiling of debris and unsuitable materials beyond normal working hours shall not be permitted. Immediately after construction operations are complete, all equipment, debris and unsuitable materials shall be completely removed from the site in order to minimize the damage to finished work and inconvenience to the public and adjoining property owners.

### **615.2 MEASUREMENT AND PAYMENT**

The Engineer will measure the street sweeping by the lump sum.

Payment for "Street Sweeping" at the contract lump sum price bid is full compensation for the specified work.