

840 - TEMPORARY SURFACING MATERIAL

840.1 DESCRIPTION

At the locations shown on the plans or as directed by the Engineer, the Contractor shall furnish, install, maintain and remove temporary surfacing material in accordance with the project phasing schedule and Section 840 of the Standard Specifications, except as otherwise modified herein.

840.2 CONSTRUCTION REQUIREMENTS

During construction, the temporary surfacing material shall be maintained to provide a smooth driving surface free of bumps and potholes. It shall be the responsibility of the Contractor to make repairs to the temporary surface at the direction of the Engineer. The temporary surfacing material shall be removed as shown in the plans or as directed by the Engineer.

Access to private drive entrances shall be maintained at all times unless otherwise specified.

840.3 MEASUREMENT AND PAYMENT

The Engineer will measure the temporary surfacing material of specified type by the ton.

Payment for "Temporary Surfacing Material" of specified type at the contract unit price bid is full compensation for the specified work. No payment will be made for temporary surfacing material placed that was not requested by the Engineer.