

## **847 - MAILBOX ADJUSTMENTS**

### **847.1 DESCRIPTION**

All work shall be done in accordance with Section 847 of the Standard Specifications, except as otherwise modified herein. This work shall consist of removing existing mailboxes and mailbox supports. When required by construction sequencing, relocate mailboxes at locations agreeable to the owner and U.S. Postal Service. Reinstall acceptable mailboxes and mailbox supports that are of as good as or better quality than the original mailbox.

### **847.2 CONSTRUCTION REQUIREMENTS**

As far as possible, no mailbox shall be finally set in a sidewalk or closer than three (3) feet to a drive apron. Final setting shall be as close as possible to the original setting.

The Contractor shall notify the local postal authority prior to performing any work pertaining to mailboxes and shall coordinate required removal, temporary settings and resetting with the local postal authority.

### **847.3 MEASUREMENT AND PAYMENT**

All work and material used in connection with the resetting of the mailboxes will be considered subsidiary to other items of construction and no direct payment will be made.