

879 - PEDESTRIAN PUSH BUTTON MODIFICATION

879.1 DESCRIPTION

This work shall include areas where the sidewalk or sidewalk ramp is removed and replaced at signalized intersections.

879.2 CONSTRUCTION REQUIREMENTS

At signalized locations, where the sidewalk or sidewalk ramp is removed and replaced, the Contractor shall verify that the pedestrian push button is within reach as shown in the Pedestrian Pushbutton detail. Adjust push button location if not meeting the requirement. Work for Pedestrian Push Button Adjustment shall include a new push button, wiring from button to base of pole, alignment of push button sign, and fill-in of existing hole in the pole. Work for Pedestrian Push Button Extension shall include an extension of appropriate length to meet the requirements shown in the Pedestrian Pushbutton detail.

879.3 MEASUREMENT AND PAYMENT

The Engineer will measure each pedestrian push button modification. The engineer will measure each pedestrian push button extension.

Payment for "Pedestrian Push Button Modification" at the contract unit price, is full compensation for the specified work. Payment for "Pedestrian Push Button Extension (6" or 12")," at the contract unit price, is full compensation for the specified work.