





LIGHT POLE ATTACHMENT SCHEDULE								
MOUNTING HEIGHT ABOVE GRADE (FT)	MOUNTING HEIGHT ON POLE (FT)	EQUIPMENT	WEIGHT LBS)	SIZE				
33	31	LED ON 2' ARM	21	0.78 SQ. FT. EPA				
33	31	LED ON 2' ARM	21	0.78 SQ. FT. EPA				
25	23	WIFI ACCESS POINT	2.1	0.57 SQ. FT. EPA				
20	18	CAMERA	11.04	9" DIA. x 16" TALL				
20	18	WALL MOUNT ARM 1' EXTENSION	1	1.0 SQ. FT. EPA MAX.				
20	18	WALL TO POLE BRACKET	0.25	1.0 SQ. FT. EPA MAX.				
6	4	WEATHERPROOF ENCLOSURE	7.4	13.32" x 11.32" x 5.60"				
6	4	CCTV MEDIA CONVERTER	0.5	INSIDE ENCLOSURE				
4.75	2.75	2" NPT CONDUIT FITTING W/ PLUG	-	-				

POLE RATING (PER AASHTO 2013): 3-SEC GUST WIND SPEED: 90 MPH MAX SEE "**LIGHT POLE ATTACHMENT SCHEDULE**" FOR POLE LOADING.

DO NOT SCALE

	TITLE: S	LIG	HT POLE ATTACHMENT SCHEDULE		QTY:
valmont V	MODEL NO.: MATERIAL: FINISH:				DWN BY: PVB CHK'D BY:
Valmont Industries, Inc. Structures Division S 20805 Eaton Ave Farmington, Minnesota 55024-7932 Phone: (651) 463-8990 (800) 899-7577 P		PROJECT: OVERLAND PARK FIRE STATION #41 SOLD TO: GRAYBAR ELECTRIC SHIP TO: P.O. NO: REP: PREMIER LIGHTING - KS/MO			APPR BY: JRB DATE: 05-31-23
**CONFIDENTIAL** The information contained in this drawing is privileged and confidential,					DWG NO: A42365
and may be protected from disclosure. Please be aware that any use dissemination of this drawing may be subject to legal restriction or sance		<b>TE</b>	REVISION DESCRIPTION	BY	PAGE: 4 / 4