

Traffic Services Division

Equipment Submittal Memorandum

April 22, 2014

TO: Brian Shields, City Traffic Engineer
Guy Alon, Civil Engineer, Sr.
Victor Godinez, Sr. Traffic Engineering Technician
Trevor Leikam, Traffic Engineering Technician
Greg Scharff, Acting Public Works Superintendent
Buck Taylor, Traffic Signal Specialist
Carl Estep, Traffic Signal Specialist
Thuan Tran, Traffic Signal Specialist
John Hightower, Traffic Signal Specialist
Tony Brenton, Street Lighting Technician
Terry Cockrell, Street Lighting Technician
Carey Seaborn, Sr. Traffic Control Technician
Dennis Torrence, Traffic Control Technician
Justin Tate, Street Lighting Technician
Ed Reyes, Engineering Technician II
Rob Allen, Maintenance Worker

Andrew Morrow, Civil Engineer I
Larry Killer, Sr. Traffic Engineering Technician
David Miller, Supervisory Civil Engineer
Ron Hyland, Transportation Project Inspector, Sr
Kenneth Boone, Construction Inspector II
Ron DeSota, Transportation Project Inspector, Sr
Marvin Furgison, Inventory Control Clerk
Ron Ditmars, PW Maintenance Supervisor
Jay Meador, PW Maintenance Supervisor
Tim Morgan, Street Lighting Technician
Jordan Dillard, Maintenance Worker, Sr
Brandon Melius, Construction Inspector II
Jerry Rogers, Sr. Traffic Control Technician
Israel Barradas, Traffic Control Technician
Jim Cannon, Construction Inspector, Sr

Please forward this information on to other interested parties that are not listed above.

FROM: Bruce Wacker, Assistant City Traffic Engineer

RE: Sky Bracket Overhead Street Name Sign Bracket for Mast Arm Mounting

REMARKS:

The Sky Bracket overhead street name sign bracket for mast arm mounting has been approved for use on Traffic Signal projects. This now replaces standard offset brackets and steel banding for the mounting of overhead street name signs.

The part number is as follows:

SBCLL-SBK-XXTK YY

Where:

LL = Cable Length (66", 90", 120" or 165")

XX = Tube Length (18", 24", 46", 60", 74", 96" or 120") Use the longest that will fit on the sign and cut short if necessary

YY = Sign Mounting Channel (8", 14" or 23") Use the longest that will fit on a sign

Cable Length Guide:

66" – for mast arm diameters ranging from 2" to 7"

90" – for mast arm diameters ranging from 8" to 11"

120" – for mast arm diameters ranging from 12" to 15"

165" – for mast arm diameters ranging from 16" to 22"