

Traffic Services Division

Material Submittal Memorandum

January 16, 2019

TO: Brian Shields, City Traffic Engineer
Shawn Gotfredson, Supervisory Civil Engineer
Guy Alon, Civil Engineer, Sr.
Brian Geiger, Civil Engineer, Sr.
Andrew Morrow, Civil Engineer, Sr.
Larry Killer, Traffic Engineering Tech, Sr.
Victor Godinez, Traffic Engineering Tech, Sr.
Janet Luessenheide, Traffic Engineering Tech, Sr.
Israel Barradas, Transportation Project Inspector II
Dennis Torrence, Transportation Project Inspector I
Michael Petty, Transportation Project Inspector I
Brandon Melius, Construction Inspector, Sr.
Mark Zarda, Construction Inspector, Sr.
Matthew Hunt, Construction Inspector I
Jesse Rhynerson, Construction Inspector I
Pam Fortun, Supervisory Civil Engineer
Arij Humeida, Civil Engineer I

Rich Profaizer, Mgr. Maintenance Operations
Greg Scharff, Public Works Superintendent
Sean Ruis, PW Maintenance Supervisor
Tony Linz, Maintenance Crew Leader
John Hightower, Traffic Signal Specialist
Thuan Tran, Traffic Signal Specialist
Justin Tate, Traffic Signal Specialist
Jeffrey Rupert, Traffic Signal Specialist
Tony Brenton, Street Lighting Technician
Tony Cook, Street Lighting Technician
Rob Allen, Street Lighting Technician
Seth Walker, Street Lighting Technician
Robert White, Traffic Control Technician
Garret Rosenbaum, Traffic Control Technician
Dylan Beshore, Traffic Control Technician
Nik Soto, Traffic Signal Technician
Marvin Furgison, Inventory Control Clerk

Please forward this information on to other interested parties that are not listed above.

FROM: Bruce Wacker, Assistant City Traffic Engineer

RE: Sky Bracket Traffic Sign Mast Arm Mounting Bracket

REMARKS:

The Sky Bracket traffic sign bracket for mast arm mounting has been approved for use on Traffic Signal projects. This now replaces standard cable for the mounting of overhead street name signs. The part number is as follows:

SS-SBLL-SBK-XXTK YY

Where:

SS = Stainless Steel Banding and Stainless Steel Hardware

SB = Standard Banding

LL = Banding Length (66", 90", 120" or 165")

XX = Tube Length (18", 24", 46", 60", 74", 96" or 120") Use the longest that will fit on the sign and cut off excess

YY = Sign Mounting Channel (8", 14" or 23") Use the longest that will fit on a sign

Banding Length Guide:

66" – for mast arm diameters ranging from 2" to 7"
90" – for mast arm diameters ranging from 8" to 11"
120" – for mast arm diameters ranging from 12" to 15"
165" – for mast arm diameters ranging from 16" to 22"

Channel Number Guide:

18" thru 46" Tubes comes with 2 channels
60" thru 74" Tubes comes with 3 channels
96" Tube comes with 4 channels

Channel Number: Use 2 channels for 18" to 46" tube; 3 channels for 60" to 74" tube; 4 channels for 96" tube.

Sign area shall not exceed 2,000 square inches per clamp.